


Tata Steel retain the right to ammend the construction and technical specifications shown on this drawing without prior notice.



The window frame can be delivered and installed alongside the Trimapanel® allowing the elevation to be completed without delay.

The window can be fitted from the inside at a later date, providing flexibility and time savings to the build program.

Framing clips and seals secure the window in place. These sections can be removed to allow replacement of the glazing element.

All support steelwork by others

TRIMAPANEL U-VALUES

70mm Core = 0.31 W/m<sup>2</sup> K.  
90mm Core = 0.24 W/m<sup>2</sup> K.  
120mm Core = 0.17 W/m<sup>2</sup> K.



**Building Systems UK**  
A Tata Steel enterprise

Technical Office - TEL : 01244 892199  
www.buildingsystemsuk.co.uk

PROJECT		Trimapanel System Typical Details	
TITLE		Integrated Window Head and Cill	
DRAWN BY	LK	SCALE	NTS
APPROVED BY	PS	TOLERANCES	
DATE	21/06/23	DRG. No.	W2-011B-03