

Tata Steel retain the right to ammend the construction and technical specifications shown on this drawing without prior notice.

A continuous run of 6mm dia high grade butyl mastic (min 25 yr guarantee)

Parapet flashing max unsuported length 200mm butt or lap jointed and sealed with two runs of continuous 4mm dia high grade butyl mastic (min 25 yr guarantee)

Self drilling self tapping primary fastener with minimum 15mm dia washers

Continuous run of 4mm dia high grade butyl mastic (25 yr warranty)

A continuous run of 6mm dia high grade butyl mastic (min 25 yr guarantee)

Sealed rivets or self drilling fasteners with sealing washers at max 450mm centres

Trisomet system

Factory made insulated gutter

All support steelwork by others

© Building Systems UK

TRIMAPANEL U-VALUES

135mm Core = 0.15 W/m² K
120mm Core = 0.16 W/m² K.
100mm Core = 0.20 W/m² K.

Psi & f-Factor

Y = W/mK.

f =

STATED CALCULATION RESULTS ARE DEPENDENT ON COMPONENTS BEING AS SHOWN
Computer Modelled in accordance with EN ISO 10211



Building Systems UK

A Tata Steel enterprise

Technical Office - TEL : 01244 892199
www.buildingsystemsuk.co.uk

PROJECT

Trimapanel System
Typical Details

TITLE

Parapet

DRAWN BY

LK

SCALE

NTS

APPROVED BY

PS

TOLERANCES

DATE

14/06/23

DRG. No.

W2-016-02